

BRUHAT BANGALORE MAHANAGARA PALIKE

BBMP/2015-16/OW/WORK_INDENT18531/CALL-2

APPROVED SCHEDULE - B

BTP/BBMP/E-PMT/03/2015-16, Date: 22-01-2016

Silting and Removing and Resetting of BS Slab and Debris Clearing in Hegadenagara East Side in Ward No. 06 Byatarayanapura Sub Division

Sl. No.	Approved Qty.	Description	Unit	Approved Tender Rates of		
				P MOHAN RAJU		
				In Figures		In Words
1	1668.45	KSRB 2-1.1: Earth work in surface excavation in ordinary soil for leveling and lowering the ground manually (other than foundation of buildings, culverts, road drains and trenches of pipe line and cables) and removing the excavated stuff to a distance not exceeding 50m and lift upto 1.5m, excavated surface leveled and neatly dressed, disposed earth to be leveled after breaking of clods and neatly dressed as per specifications, Specification No KBS 2.1(a) / 2.3.1, P. No. 5/ Item No. 2.1/ PWD SR 2015-16	cum	157.0	261946.65	Rupees One Hundred Fifty Seven Only
2	2640	Removing B.S Slab of Drain and stacking Page No. 25/ Item No. 5.32/ PWD SR 2015-16	Sqm	62.0	163680.00	Rupees Sixty Two Only
3	2640	Refixing stone slabs of drains and pointing in C.M (1:3) Page No. 25/ Item No. 5.33/ PWD SR 2015-16	Sqm	75.0	198000.00	Rupees Seventy Five Only
4	660	Providing granite slabs of selected quality roughly dressed and fixed in cement mortar(1:6) including fixing curing etc, complete -do- 7.5 cms thick Page No. 28/ Item No. 5.31.1/ PWD SR 2015-16	Sqm	662.75	437415.00	Rupees Six Hundred Sixty Two and Seventy Five Paise Only
5	1668.45	Lead for Disposal of Debris shall be payable at carage rates by Mechanical means including loading and unloading. From 0.00 to 2.00 Km (Page No.123,	Cum	62.0	103443.90	Rupees Sixty Two Only

P. Mohan Raju
Signature of the Contractor

H.V. V. V.
Executive Engineer
Byarayanapura Division
BBMP, Bangalore - 92
11/3/16
Jun 01/03